



NOTICE OF APPROVAL

The Department of Community Planning & Building of the City of Carmel-by-the-Sea has approved a Project pursuant to the City's Municipal Code. Persons interested in the project may review additional materials available at the Department of Community Planning & Building located at City Hall on Monte Verde Street between Ocean and 7th Avenues, phone number 831-620-2010.

The decision to approve this project may be appealed within 10 days from the date of this by filing a written appeal with the Department of Community Planning & Building.

Planning Case #: Design Study 24347

Owner Name: DEARBORN JOHN T & DANIELLE P TRS

Case Planner: Jacob Olander, Associate Planner

Date Posted: _____

Date Approved: 02/25/2025

Project Location: Dolores St. 4SW of 10th Ave.

APN #: 010158005000 **BLOCK/LOT:** 115/ALL LOT 9

Applicant: Carol Brock/Masterwork Builders

Project Description: This approval of Design Study DS 24347 (Dearborn) authorizes a project to amend DS 24128(Dearborn) for new landscape planting, a gas fire pit, granite paving path, a wood fence, and other siteimprovements located at Dolores St. 4SW of 10th Ave. in the Residential District and, APN: 010158005000 asdepicted in the plans stamped approved by Community Planning and Building Department on 02/25/2025 unless modified by the conditions of approval contained herein.

Can this project be appealed to the Coastal Commission? Yes No

Upon completion of the 10 calendar-day appeal period, please return this form, along with the Affidavit of Posting, to the case planner noted above.



FINDINGS AND CONDITIONS

Project: DS 24347 (Dearborn)

Location: Dolores St. 4 SW of 10th Ave.; 010-158-005-000

Date of Action: February 25, 2025

Project Description:

DS 24347 (Dearborn) authorizes the approval of Design Study Application (DS 24347, Dearborn) amending the Design Study Approval, DS 24128 (Dearborn), for work on the subject site located at Dolores St. 4 SW of 10th Ave. in the Single-Family (R-1) District. APN: 010-158-005-000.

The proposed changes include:

- new landscape planting,
- a gas fire pit,
- a granite paving path,
- a wood fence, and
- other site improvements.

FINDINGS REQUIRED FOR DESIGN STUDY APPROVAL		
The Director shall have the authority to approve, approve with modifications and/or conditions, or deny an application for design review based on written findings stating the reasons for the action. Findings shall be based on information in the record. CMC 17.58.060.A.		
For each of the required findings listed below, the staff has indicated whether the application, either as proposed or with conditions, supports adopting the findings. For all findings checked "no," staff discusses the issues to facilitate staff's decision-making. Findings checked "yes" may or may not be discussed depending on the issue(s).		
CMC 17.58.060.B Findings for Design Review Approval	YES	NO
Before approving an application for design review in any district, the Director shall find that the final design plans:		
1. Conform to the applicable policies of the General Plan and the Local Coastal Program;	✓	
2. Comply with all applicable provisions of this code; and	✓	
3. Are consistent with applicable adopted design review guidelines.	✓	
Additional Staff Analysis/Discussion: No additional staff analysis.		

ENVIRONMENTAL REVIEW
The California Environmental Quality Act (California Public Resources Code §§ 21000, <i>et seq.</i> , "CEQA"), together with State Guidelines (14 California Code Regulations §§ 15000, <i>et seq.</i> , the "CEQA Guidelines") and City Environmental Regulations (CMC 17.60) require that certain projects be reviewed for environmental impacts and that environmental documents be prepared.
Finding: The Community Planning and Building Department finds that pursuant to CEQA regulations, the project is categorically exempt under Section 15301 (Class 1) – Existing Facilities, and no exceptions to the exemption exist pursuant to section 15300.2 of the CEQA Guidelines.
Additional Staff Analysis/Discussion: The proposed changes include: <ul style="list-style-type: none"> • new landscape planting, • a gas fire pit, • a granite paving path, • a wood fence, and • other site improvements.

CONDITIONS OF APPROVAL	
No.	Standard Conditions
1.	Authorization. This approval of Design Study DS 24347 (Dearborn) authorizes a project to amend DS 24128 (Dearborn) for new landscape planting, a gas fire pit, granite paving path, a wood fence, and other site improvements located at Dolores St. 4SW of 10th Ave. in the Residential District and, APN: 010158005000 as depicted in the plans stamped approved by Community Planning and Building Department on 02/25/2025 unless modified by the conditions of approval contained herein.
2.	Codes and Ordinances. The project shall be constructed in conformance with all requirements of the Residential zoning district. All adopted building and fire codes shall be adhered to in preparing the working drawings. If any codes or ordinances require design elements to be changed, or if any other changes are requested when such plans are submitted, such changes may require additional environmental review and subsequent approval by the Planning Commission.
3.	Permit Required. <input checked="" type="checkbox"/> A Building Permit shall be applied for and obtained from the Building Division prior to commencement of work. The Building Permit shall be applied for in a manner consistent with the submittal requirements prescribed by the Building Division. <input type="checkbox"/> A building permit is not required; however, the applicant shall apply for and obtain a Notice of Authorized Work from the Building Division prior to commencement of work. To apply for the Notice of Authorized Work, please submit the Scope of Work Declaration through the city's online permit portal .
4.	Permit Validity. The project shall be implemented in accordance with the time limits set forth CMC 17.52.170 (Time Limits on Approvals and Denials) . During this time, the project must be implemented, or the approval becomes void. Implementation is effected by erecting, installing, or beginning the installation of the improvement authorized by the permit, as determined by the Director. Extensions to this approval may be granted consistent with CMC 17.52.170.C.
5.	Water Use. Approval of this application does not permit an increase in water use on the project site without adequate supply. Should the Monterey Peninsula Water Management District determine that adequate water is unavailable for this site, this approval shall be null and void. If installed, the property owner/applicant shall be required to remove the subject improvement(s) at the property owners expense.
6.	Modifications. The Applicant shall submit in writing, with revised plans, to the Community Planning and Building staff any proposed changes to the approved project plans prior to incorporating those changes. If the Applicant changes the project without first obtaining City approval, the Applicant will be required to submit the change in writing, with revised plans, within two weeks of the City being notified. A cease work order may be issued at any time at the discretion of the Director of Community Planning and Building until a) either the Planning Commission or Staff has approved the change, or b) the property owner has eliminated the change and submitted the proposed change in writing, with revised plans, for review. The project will be reviewed for its compliance with the approved plans prior to the final inspection.
7.	Indemnification. The Applicant agrees, at his or her sole expense, to defend, indemnify, and hold harmless the City, its public officials, officers, employees, and assigns from any liability; and shall reimburse the City for any expense incurred, resulting from, or in connection with any project approvals. This includes any appeal, claim, suit, or other legal proceedings to attack, set aside, void, or annul any project approval. The City shall promptly notify the Applicant of any legal proceeding and cooperate fully in the defense. The City may, at its sole discretion, participate in any such legal action, but participation shall not relieve the Applicant of any obligation under this condition. Should any party bring any legal action in connection with this project, the Superior Court of the County of Monterey, California, shall be the situs and have jurisdiction for resolving all such actions by the parties hereto.
8.	USA North 811. Prior to any excavation or digging, the Applicant shall contact the appropriate regional notification center (USA North 811) at least two working days, but not more than 14 calendar days, prior to commencing that excavation or digging. No digging or excavation is authorized to occur on-site until the Applicant has obtained a Ticket Number and all utility members have positively responded to the dig request. (Visit USANorth811.org for more information)

9.	<p>Conditions of Approval. Prior to the issuance of a Building Permit or Notice of Authored Work, the Applicant shall print a copy of the signed Conditions of Approval within the construction plan set submitted to the Building Safety Division as part of the submittal for the Building Permit Application or Notice of Authorized Work.</p>
10.	<p>Tree Removal Prohibited. Throughout construction, the Applicant shall protect all trees identified for preservation by methods approved by the City Forester. Trees on or adjacent to the site shall only be removed or pruned with the approval of the City Forester or Forest and Beach Commission.</p>
11.	<p>Tree Protection Measures. Requirements for tree preservation shall adhere to the following tree protection measures on the construction site.</p> <ul style="list-style-type: none"> • Prior to grading, excavation, or construction, the contractor/builder shall clearly tag or mark all trees to be preserved. • Excavation within 6 feet of a tree trunk is not permitted. • No attachments or wires of any kind, other than those of a protective nature, shall be attached to any tree. • Per Municipal Code Chapter 17.48.110, no material may be stored within the dripline of a protected tree, including the drip lines of trees on neighboring parcels. • Tree Protection Zone. The Tree Protection Zone shall be equal to dripline or 18 inches radially from the tree for every one inch of trunk diameter at 4.5 feet above the soil line, whichever is greater. A minimum of 4-foot-high transparent fencing is required unless otherwise approved by the City Forester. Tree protection shall not be resized, modified, removed, or altered in any manner without written approval. The fencing must be maintained upright and taught for the duration of the project. No more than 4 inches of wood mulch shall be installed within the Tree Protection Zone. When the Tree Protection Zone is at or within the drip line, no less than 6 inches of wood mulch shall be installed 18 inches radially from the tree for every one inch of trunk diameter at 4.5 feet above the soil line outside of the fencing. • Structural Root Zone. The Structural Root Zone shall be 6 feet from the trunk or 6 inches radially from the tree for every one inch of trunk diameter at 4.5' above the soil line, whichever is greater. Any excavation or changes to the grade shall be approved by the City Forester prior to work. Excavation within the Structural Root Zone shall be performed with a pneumatic excavator, hydro-vac at low pressure, or another method that does not sever roots. • If roots greater than 2 inches in diameter or larger are encountered within the approved Structural Root Zone, the City Forester shall be contacted for approval to make any root cuts or alterations to structures to prevent roots from being damaged. <p>If roots larger than 2 inches in diameter are cut without prior City Forester approval or any significant tree is endangered as a result of construction activity, the building permit will be suspended, and all work stopped until an investigation by the City Forester has been completed, and mitigation measures have been put in place. The Forester can be reached at 831-620-2073.</p>
12.	<p>Foundation Work Near Significant Trees. All foundations within 15 feet of significant trees shall be excavated by hand. If any tree roots larger than two inches (2") are encountered during construction, the City Forester shall be contacted before cutting the roots. The City Forester may require the roots to be bridged or may authorize the roots to be cut. If roots larger than two inches (2") in diameter are cut without prior City Forester approval or any significant tree is endangered as a result of construction activity, construction activity will be suspended and all work stopped until an investigation by the City Forester has been completed. The Forester can be reached at 831-620-2073.</p>

SPECIAL CONDITIONS	
13.	Building Permit Revision. A revision to BP 23-208 (Dearborn) is required prior to commencement of work.
14.	Prior Conditions of Approval. All conditions of approval of the previous Design Study approval(s) shall also apply to this approval unless expressly otherwise noted within these Conditions of Approval. Further, the previous approval remains in full force and effect unless otherwise modified by this action.
15.	
16.	
17.	

*Acknowledgement and acceptance of conditions of approval.

Property Owner Signature

Printed Name

Date


Applicant Signature

Printed Name

Date

Once signed, please email to jolander@ci.carmel.ca.us.

H-STYLE CFBH200 - For 40" x 17" opening or larger



SKU (NG OR LP)	DESCRIPTION	SHIP WEIGHT	SHIP METHOD
CFBH200NG CFBH200LP	200K BTU H-Style Brass Burner + WATERSTOP	9 lbs	SHIPS PARCEL
Recommended parts - Plate: ALPL4017 • FK1 • Optional 6x Support Collars			
CFBH200NGALPL4017 CFBH200LPALPL4017	with 40" x 17" Rectangular Plate	18 lbs	SHIPS PARCEL
CFBH200NGALPL4017FK1 CFBH200LPALPL4017FK1	with 40" x 17" Plate + FK1	21 lbs	SHIPS PARCEL

FIREPIT BURNER SPEC



ENTRY GATE INSPIRATION



DRY STACKED STONE WALL INSPIRATION



LEGEND

- ASPHALT PAVING: TO MATCH EXISTING DRIVEWAY PAVING SECTION.
- STONE COBBLE: 5" SQUARE FOND DU LAC COBBLE - WET SET OVER 6" CONCRETE SUB-SLAB OVER COMPACTED BASE ROCK AND SUBGRADE.
- MULCH
- GARDEN WALL: CMU WITH BRICK VENEER - BRICK TYPE TO BE LIRO. AVAILABLE FROM ECO OUTDOORS.
- DRY STACKED STONE RETAINING WALL
- FENCE
- HDR METAL EDGE
- PLT PLANTING AREA

REFERENCE NOTES

- ① REINSTALL EXISTING WATER FEATURE - PLUMB WITH AUTOFILL, OVERFLOW AND LIGHTING.
- ② GAS FIREPIT WITH AUTO IGNITER - CMU WITH STUCCO FINISH - COLOR AND FINISH TO MATCH HOUSE.
- ③ LEFT BLANK
- ④ MOVABLE BBQ
- ⑤ LEFT BLANK
- ⑥ WOOD FENCE AND GATE AT TRASH ENCLOSURE - 6' HIGH
- ⑦ STEPS WITH METAL RISERS AND MULCH TREADS
- ⑧ TRELLIS OVER ENTRY GATE
- ⑨ GRANITE PLANK PAVING STONE - LENGTHS VARY - WET SET OVER MUD SETTING BEDS
- ⑩ GRANITE PLANKS ON FRONT PORCH - WET SET OVER CONCRETE SUB SLAB.
- ⑪ INSTALL GRANITE SLAB ON VERTICAL RISER - SAW CUT AND FIELD FLAME AND CHIP LEADING EDGE OF TREAD AT STEP.

SHEET INDEX

SHEET NO:	CONTENTS:
L-1.0	SITE PLAN
L-2.0	GRADING PLAN
L-3.0	PLANTING NOTES
L-4.0	SITE LIGHTING PLAN

PROPOSED LOT COVERAGE

LOT COVERAGE ALLOWED: 396.0 SF
 BONUS SITE COVERAGE: 160 SF
 TOTAL COVERAGE ALLOWED: 556 SF

	AREA (SF)	
IMPERMEABLE		
FIREPIT (IMPERMEABLE)	14.1 SF	
WALLS (IMPERMEABLE)	23.2 SF	
DRIVEWAY (IMPERMEABLE)	99.4 SF	
FRONT PORCH	53.4 SF	
WATER FEATURE	7.9 SF	
SUBTOTAL (IMPERMEABLE)	198 SF	36%
PERMEABLE		
ENTRY WALK (PERMEABLE)	99.8 SF	
WOOD DECK (PERMEABLE)	253.5 SF	
TRELLIS	4.5 SF	
SUBTOTAL (PERMEABLE)	357.8 SF	64%
TOTAL PROPOSED COVERAGE	555.8 SF	

PROJECT NAME:

DEARBORN
 RESIDENCE

PROJECT ADDRESS:

DOLORES 4 SW OF 10TH
 CARMEL, CA 93921

APN: 010-158-005-000

ISSUANCE:

BUILDING DEPARTMENT
 SUBMITTAL

PROJECT NO: 2024-22
 DATE: 09/27/2024


REVISIONS:

DATE	DESCRIPTION
10/24/2024	CITY RESUBMITTAL
01/08/2025	CITY RESUBMITTAL

SHEET NAME:

SITE PLAN

SHEET NO:



SCALE: 1/4" = 1'-0"

